



PLANNING COMMISSION STAFF REPORT

FOR CONSIDERATION BY PLANNING COMMISSION ON JUNE 23, 2026

FOUNDERS RIDGE – DESIGN PLAN

APPLICANT: McGill Smith Punshon, Inc. (James H. Watson)
3700 Park 42 Drive, Suite 190B
Cincinnati, OH 45251

OWNER: RK Development
1789 Stable Trails
Amelia, OH 45102

ENGINEER: McGill Smith Punshon, Inc. (James H. Watson)
3700 Park 42 Drive, Suite 190B
Cincinnati, OH 45251

REQUEST: Requesting approval from the Clermont County Planning Commission for Founders Ridge – Design Plan

LOCATION: The subject property (PIN 032019B005) is located off of State Route 132.

HISTORY: No relevant history regarding the subject property.

DEVELOPMENT PROPOSAL:

Founders Ridge – Design Plan consists of +/- 70.102 acres and proposes +/- 38.013 acres to be subdivided in multiple phases. The subject property is currently a vacant, wooded lot adjacent to residential and institutional land uses. The proposed land use is detached single-family residences, which will compliment the existing land use pattern within the area. The total area is +/- 38.013 acres, and will include 5 nonbuildable, open-space lots totaling +/- 11.539 acres (or 30.3%) and +/- 5.251 acres of proposed area within new R/W. The project proposes a residential lot yield of 74 residential lots with the density proposed to be +/- 1.95 dwelling units per acre. There is an additional +/- 32.089 acres for potential future development.

DEVELOPMENT DATA:

Current Zoning: “PD” Planned Development District

Total Lots: 79

Area in Lots: +/- 21.223 acres

Area in Open Space: +/- 11.539 acres

Total Site Area: +/- 38.013 acres

Area in R/W: +/- 5.251 acres

Density: +/- 1.95 du/a

School District: West Clermont Local School District

Homes:

Number of Units: 74 Units

Min. Lot Area: +/- 10,000 sq. ft.

Front Yard Setback: 35 ft.

Rear Yard Setback: 35 ft.

Min. Lot Width: 70 ft.

Side Yard Setback: 5’/20’

SITE ACCESS:

The street system extends from State Route 132 across from Stable Trails, an existing private street. A traffic impact study has been approved by ODOT with the finding that a southbound left turn lane into the site is warranted. Sidewalks are proposed along both sides of the subdivision streets.

STAFF ANALYSIS:

Per the review of Founders Ridge – Design Plan, the development will follow all requirements pertaining to Article V of the *Clermont County Subdivision Regulations* based on conditions noted in the Design Plan Comment Review Meeting. The proposed subdivision is an expected development and complements the land uses of the surrounding area. There are a number of conditions that must be met regarding the development. Departmental comments are below and the applicant and developer are aware of the requirements in order for this subdivision to be constructed.

Clermont County Community & Economic Development Comments:

1. Any future development of the site must comply with any and all regulations from Clermont County, Batavia Township, the State of Ohio, or any other applicable agency.

Clermont County Engineer's Office Comments:

1. Ohio Department of Transportation (ODOT) APPROVAL is needed for all proposed improvements within, along, or impacting the State Route 132 Right-of-Way. Documentation of APPROVAL, from ODOT, needs to be provided for the proposed site modifications, prior to the approval of construction drawings.
2. A general reminder regarding roadway geometry; the minimum allowable street grade is 0.4%, maximum street grade is 12% (10% preferred), and the minimum

centerline curve radius is 200

Clermont County Water Resources Department Comments:

Currently has no comments. Further reviews will be done at the time of the construction plan submittal.

Clermont County W.M.S.C. Comments:

WMSC has several comments for the future construction documents and plans that will need to be addressed.

1. Best Management Practices (BMPs): Provide all applicable WMSC BMPs on the construction drawings. This shall include, but not be limited to, silt fence, sediment and erosion control measures, temporary construction entrances, and the location of any temporary sediment basins.
2. Lot Layout and Drainage Details: Provide a detailed lot layout, including drainage swale details and AA ditch details between each lot. The plans must clearly demonstrate that drainage will be directed away from all structures and conveyed to an appropriate and stable drainage outlet.
3. Drainage Easements and Overland Flood Routes: All drainage easements and overland flood routes shall be clearly identified on the plans. Include a note stating that no development, grading, or obstruction may occur within any designated drainage easement.
4. Downstream Analysis: Provide a downstream culvert analysis, including all supporting hydrologic and hydraulic calculations, demonstrating that downstream infrastructure is adequate to convey the proposed runoff.
5. Minimum Opening Elevations (MOEs): Provide MOEs for all applicable lots where required, and clearly identify them on the plans.
6. Stormwater Infrastructure Details: Provide all applicable stormwater infrastructure details for the project, including but not limited to pipe details, structures, outlet protection, and any related appurtenances.
7. As-Built Certification Requirement: Please be advised that, upon completion of site development, a complete set of Basin As-Built Certification drawings shall be required in accordance with WMSC Regulations, Section 710. Additionally, final site inspection approval must be obtained before the WMSC Division of the Building Department signs and dedicates the final record plat.

Soil and Water Conservation District Comments:

1. A downstream hydraulic analysis should be conducted for the Lot 1 stormwater basin discharge
2. Geotechnical reports will be needed for all construction on EbG2 soil


STAFF RECOMMENDATION:

Based on Staff Analysis, request a motion to **APPROVE** the Founders Ridge – Design Plan with the following conditions:

1. All county and township departments' comments and conditions detailed in the staff report be addressed.
2. Any future development of the site must comply with any and all regulations from Clermont County, Batavia Township, the State of Ohio, or any other applicable agency.

PARCEL MAP

Founders Ridge



PROPERTY INFORMATION


Parcel Numbers: 032019B005

Total Site Area: +/- 70.102 Acres



ZONING MAP

Founders Ridge



PROPERTY INFORMATION

Parcel Numbers: 032019B005

Total Site Area: +/- 70.102 Acres



**CLERMONT COUNTY PLANNING COMMISSION
APPLICATION FOR DESIGN PLAN REVIEW**

Date May 28, 2026 A/P # _____

Name of Subdivision Founders Ridge

Location 3588 State Route 132
Amelia, OH 45102

Township Batavia Military Survey 586

Complete Parcel Identification Number (PIN) 0320019B005

Have **ALL** Concept Plan Review Letters been Obtained? yes
(See Design Plan Review Required Items Checklist, provide Documentation upon submittal)

Name of Applicant James H. Watson, McGill Smith Punshon, Inc,

Address 3700 Park 42 Drive, Suite 190B

City Cincinnati State OH Zip 45241

Phone (513) 759-3205 Fax _____ Email jwatson@mspdesign.com

Name of Owner of property to be subdivided RK Development

Address 1789 Stable Trails

City Amelia State OH Zip 45102

Phone (513) 543-7120 Fax _____ Email rgkemper1@roadrunner.com

Name of applicant's surveyor or engineer McGill Smith Punshon, inc

Address 3700 Park 42 Drive, Suite 190 B

City Cincinnati State OH Zip 45241

Phone (513) 759-3205 Fax (513) 563-7099 Email jwatson@mspdesign.com

Acreage owned 70.102 Acreage proposed to be subdivided 38.013

Current Zoning Classification PD Planned District

Proposed Zoning Changes none

Proposed Land Use single family residences

Is this a proposed "Special Development"? (See Article VII Sub Reg's) no
(If yes, please attach completed "Special Development" Form)

DEVELOPMENT CHARACTERISTICS:

Number of proposed lots 74 Typical lot width 75'

Number of proposed unit's none Typical lot area 10,000 sf

Single Family 74 Multi-Family none

Acreage to be devoted to recreation, parks or open space 11.539

Recreation facilities to be provided passive open space, community park, water features

Proposed method of supplying water service extension of existing county water lines

Proposed method of sanitary waster disposal extension of existing county sewer lines

(If on-site disposal systems are proposed, please attach letter certifying Board of Health approval).

May 28, 2026

Mr. Drew DeMarsh, AICP
Clermont County Community & Economic Development
101 East Main Street
Batavia, OH 45103

Re: Proposed Founders Ridge Subdivision
3588 State Route 132, Batavia Township
Request for Design Plan Approval

On behalf of the future owner and developer, M/I Homes of Cincinnati, LLC, we are pleased to present the attached Design Plan for the subject location. The property, identified as tax parcel 03219B005, contains 70 acres, of which 38 acres is planned to be subdivided. The proposed use will be 74 single family homes situated on 75-foot-wide lots. At this time, development of the balance of the property is not planned


A total of 11.5 acres will remain as open space, comprising 30 percent of the project. The open spaces, entrance features and other amenities will be owned and maintained as a part of a homeowners' association.

The street system extends from State Route 132 across from Stable Trails, an existing private street. A traffic impact study has been approved by ODOT with the finding that a southbound left turn lane into the site is warranted. Sidewalks are proposed along both sides of the subdivision streets. Sanitary sewer is proposed to extend from existing county sewers located west of the property. Water service will extend from existing facilities along State Route 132. Stormwater detention and water quality requirements will be addressed by utilizing three proposed ponds located throughout the site.

We request consideration of this application at the Planning Commission's June 2026 meeting. Until then, please review the plan and contact us with any questions and comments. Thanks very much for your time and consideration of this application.

Sincerely,

McGill Smith Punshon, Inc.



James H. Watson, P.E.
Executive Vice President

Cc: Justin Lanham, M/I Homes of Cincinnati, LLC



Project Manager JHW
Drawn By DA
DWG 02514004-DES-2026
X-Ref(s) 0251400-BDY-00
02514003-TOP-AER-SR132

Issue/Revision	No.	Date
CONCEPT PLAN		05/01/26
DESIGN PLAN		05/28/26

© Copyright 2026, MCGILL SMITH PUNSHON, INC.



James H. Watson

**FOUNDERS RIDGE
DESIGN PLAN**
**SCOTT MILITARY SURVEY No. 586
BATAVIA TOWNSHIP
CLERMONT COUNTY, OHIO**

Sheet Title

SITE PLAN


Project Number 02514.40
Drawing Scale 1" = 100'
Sheet Number C2
File Number 02514



UNLESS OTHERWISE DESIGNATED ON THE RECORD PLAT, A (10) FOOT WIDE DRAINAGE EASEMENT SHALL EXIST ALONG ALL COMMON LOT LINES. THE COMMON LOT LINE BEING THE CENTER OF SAID DRAINAGE EASEMENT.



N:\land projects\02000\02514\dwg\02514004-DES-2026.dwg, C3, 5/27/2026 10:05:48 PM, hkh@mcn




MSP
DESIGN
McGill Smith Punshon

■ Architecture 3700 Park 42 Drive
■ Engineering Suite 190B
■ Landscape Architecture Cincinnati OH 45241
■ Planning Phone 513.759.0004
■ Surveying www.mspsdesign.com

Project Manager JHW
Drawn By DA
DWG 02514004-DES-2026
X-Ref(s) 0251400-BDY-00
02514003-TOP-AER-SR132

Issue/Revision	No.	Date
CONCEPT PLAN		05/01/26

© Copyright 2026, MCGILL SMITH PUNSHON, INC.



**FOUNDERS RIDGE
DESIGN PLAN**

**SCOTT MILITARY SURVEY No. 586
BATAVIA TOWNSHIP
CLERMONT COUNTY, OHIO**

Sheet Title

**ORIGINAL
CONDITION PLAN**

Project Number 02514.00
Drawing Scale 1" = 100'
Sheet Number C3
File Number 02514